pay up the balance in instalments of not less than Rs. 1,000, provided the full value is paid not later than the 15th May 1925. The monies shall be paid into such treasury as the District Forest Officer may direct, within the time specified.

8. If the amount is not fully paid for by the purchaser before the dates fixed above, the initial deposit as well as the other monies already paid in, shall be forfeited to Government and all or any portion of the timber not fully paid for shall be resold at the risk of the purchaser in the manner prescribed for default of payment of one-tenth value in clause 5 *supra*.

9. No timber lot shall be permitted to be removed by the purchaser unless it has been paid for in full, calculated at the rates at which the timber is knocked down to him at the time of sale, excluding the 10 per cent deposit paid for the lot at the time of the sale; and no timber shall be removed from the depot unless a permit is obtained from the Forest Officer in charge of the depot. The earnest money will not be adjusted towards the value of timber, until 90 per cent of the purchase money over and above the security deposit has been paid.

10. Timber purchased should be removed as early as possible and in no case should it be allowed to remain longer than 90 days after the dates fixed in clause 7 *supra*. Timber not removed after purchase will remain in the depot at the risk of the purchaser from the date of the confirmation of the sale.

11. If the timber is not removed within the time allowed, the same may, after ten days' notice to the purchaser, be sold in public auction and the proceeds will be given to the purchaser after defraying all the expenses in connection with the resale.

12. The deposit of Rs. 200 will remain as security for the due fulfilment of all and every one of the terms of sale, on the breach of any of which by the purchaser, the District Forest Officer shall be entitled to forfeit the deposit in whole or in part and in the event of such forfeiture, the sum so forfeited shall be immediately made good by the purchaser so long as the transaction is not finally closed. The security deposit or the balance thereof, if any, shall be returned to the purchaser after the full value of timber purchased has been paid for and the timber fully removed.

K. REVANNA,
District Forest Officer.

BHADRAVATI DIVISION.

Abstract Notification.

The attention of the public is invited to the Notification dated 1st February 1925 published in pages 124 and 125 Part VI of the *Mysore Gazette* dated 12th February 1925 calling for tenders for the right of collecting the fallen dry timber and logs and tops of felled trees of the State Forests of the Bhadravati Division.

C. ABDUL JABBAR,
For *District Forest Officer*.

ENGINEERING DEPARTMENT.

CHITALDRUG DIVISION.

Dated 7th February 1925.

FORM OF ADVERTISEMENT.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 5th March 1925, for constructing a Maternity attached to the Civil Hospital and for improving the facade of the existing Civil Hospital at Chitaldrug.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1925.

2. The plan and detailed estimate and conditions may be seen at the Office of the Executive Engineer at Chitaldrug the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government currency notes as earnest money, and be superscribed "Tender for constructing a Maternity attached to the Civil Hospital and for improving the facade of the existing Civil Hospital at Chitaldrug.

5. The final acceptance of any tender will rest with the Chief Engineer who does not bind himself to accept the lower or any tender or to assign any reason whatever for the rejection of any tender.

6. In matter of all disputes about rates, measurements, quality of works, etc., and in all disputes of any kind the decision of the Chief Engineer will be final and legally binding.

7. Within eight days of acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered as cancelled and his earnest money will be forfeited.

8. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

9. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for constructing Maternity attached to the existing Civil Hospital at Chitaldrug and improving the facade of the existing Civil Hospital :—

Serial No.	Items of work	Unit	Quantity
	IMPROVING THE FRONT ELEVATION OF EXISTING BUILDING.		
1	Removing the existing ornamental work in front wall of office and compounding room.	Each	2
2	Burnt brick in chunam pediments	R. ft.	30
3	Do hood cornices	"	50
4	Do parapet 2½' feet high including plastering	"	63½
5	Light cornice	"	43
6	Masonry or wooden railings	"	18
	MATERNITY AND WARDS.		
1	Earthwork excavating foundation in hard gravelly soil and filling basement ..	Cyd.	222
2	Concrete in chunam	C. ft.	2,695
3	Stone in mortar	"	3,625
4	Burnt brick in chunam	"	5,296
5	Burnt stone slabs 6" thick dressed	S. ft.	1,335
6	Chunam plastering	S. qr.	88·14
7	Teakwood panelled doors with bolts, hinges, etc., complete	S. ft.	341
8	Do windows with glazed shutters inside and panelled shutters outside with 4 halves and iron bars with hinges, hooks, rings, etc, complete	"	270 168
9	Teakwood glazed ventilators with cross iron bars, etc., complete	"	
10	Teakwood cupboards panelled with cross planks, etc., complete	"	41
11	Cut stone pillars (7½' x 8" x 8") with base and capitals	Each	32
12	Rolled steel girders with Railway freight and fining	C. wt.	36
13	Teakwood wrought and put up with wood oiling	C. ft.	24·36
14	Roofing with 1st class Mangalore tiles on teak reepers 2" x 1"	S. qr.	3 78
15	Ridge tiles set in mortar	R. ft.	21
16	Pakka terraced roofing	S. qr.	29·63
17	Flooring with first class Mangalore square tiles on 3" concrete bed and cement pointing	"	7·60
18	Flooring with 2" think Cuddapah slabs on 3" concrete and cement pointing ..	"	15·20
19	White and colourwashing 2 coats	"	88·14
20	Silicate blue painting 2 coats	"	29·37
21	Cornice work 9" x 1"	R. ft.	427
22	Light cornice with ornamental work over ventilators	"	288
23	Brick in chunam ornamental parapet 2½' x 9"	"	128
24	Do do 2' high	"	295
25	Ornamental finials masonry	Each	52
26	Moulding the name with ornamental works over parapet "Civil Hospital" ..	L. S.	
27	Masonry or wooden railings in front verandah	R. ft.	120
28	Constructing "¼V" shaped slabbed drain with concrete at bottom and cement pointing to joints.	"	230
29	Fixing zinc rain down pipes 4" dia and 4 feet long	Each	30
30	Providing squatts pattern plates for seats to latrine with masonry bases ..	"	4
31	Constructing cement drains to carry urinals with cement plastering	R. ft.	15
32	Providing water tap and pipe line in closets	"	100
33	Providing lavatory basins	Each	1
34	Removing old window and fixing new door and repairing the same with plastering	L. S.	
35	Teakwood gate with iron hinges as per plan with gate, etc.	"	"
36	Chunam pointing	S. qr.	3·00
37	Tarring to wood work	L. S.	
38	Clearing site and levelling ground	"	"
39	Unforeseen charges such as providing windows cross walls in old building ..	"	"

A. TANDONI RAO,
Executive Engineer.